

## Requirements for Underground Electric Service

- All Trench work or digging is the responsibility of the consumer. The specifications for the ditch are as follows:
  - Primary Line: Ditch must be 4 feet in depth.
  - Secondary Line: Ditch must be 3 feet in depth.
  - For wire not in pipe (we will give notice), the following will apply:
    - *6 inches of sand in the bottom*
    - *6 inches of sand over the wire.*
    - *No Screenings.*
  - Consumer must provide conduit, if needed, for road &/or driveway crossings, etc.
- LREC must have a 48-hour notice of planned digging for scheduling purposes.
- Site must be inspected and approved 24 hours prior to installation.
- Consumer must provide trenching/backfilling equipment. Backhoe and operator must be present and ready when LREC crew arrives at the scheduled time to install the cable. **If the consumer is not able to provide the equipment and the operator for the scheduled date and time, he or she must notify LREC before the crew leaves the warehouse in the morning in order to avoid any service charge. Otherwise, the following charges will be applied to the consumer's account:**
  - **Crew arrives on job site and the consumer's equipment and/or operator is delayed and not available.....\$180.00 per hour until equipment and operator arrive.**
  - **Crew arrives on job site and job is rescheduled due to lack of equipment or operator.....Travel & restocking Rate of \$540.00 (\$180.00 @ 3 hours)**
- Backhoe must be present and ready when we arrive at the scheduled time (You must provide the equipment and the operator!)

**PLEASE CONTACT LREC, ENGINEERING DEPARTMENT, TO SCHEDULE A TIME FOR DIGGING OF DITCH. (918) 772-2526 OR (800) 364-5732**

I have been informed of LREC Underground procedures & have received a copy of this form.

Consumer's Name (print): \_\_\_\_\_

Consumer's Signature: \_\_\_\_\_

Staking Engineer: \_\_\_\_\_